HIC-LC3-24 Interim Results

Synthetic training content. Not a real Holcim trial report.

HIC-LC3-24 Interim Results

This file owns mix numbers. If a mix is not listed, write Not found.
Do not average rows. Do not use typical LC3 values from outside this file.

28-day compressive strength (EN 196-1, synthetic)

Mix M01 | CEM I control | clinker factor 0.95 | calcined clay 0 percent | 52.4 MPa | spec 42.5 MPa | Pass
Mix M02 | CEM I control | clinker factor 0.95 | calcined clay 0 percent | 51.1 MPa | spec 42.5 MPa | Pass
Mix M07 | CEM II/A-LL | clinker factor 0.73 | calcined clay 0 percent | 46.2 MPa | spec 42.5 MPa | Pass
Mix M08 | CEM II/A-LL | clinker factor 0.71 | calcined clay 0 percent | 44.8 MPa | spec 42.5 MPa | Pass
Mix M12 | LC3-50 | clinker factor 0.52 | calcined clay 30 percent | 44.8 MPa | spec 42.5 MPa | Pass
Mix M13 | LC3-50 | clinker factor 0.50 | calcined clay 31 percent | 41.2 MPa | spec 42.5 MPa | Fail
Mix M18 | LC3-50 | clinker factor 0.54 | calcined clay 29 percent | 45.6 MPa | spec 42.5 MPa | Pass
Mix M21 | LC3-35 | clinker factor 0.65 | calcined clay 20 percent | 47.1 MPa | spec 42.5 MPa | Pass

Other ages in this file
Mix M12 | 7 days | 31.4 MPa | no 7-day spec in the protocol
Mix M12 | 1 day | 12.8 MPa | no 1-day spec in the protocol

Pending
90-day cubes for Mix M13 and Mix M18 are still in the fog room. Do not report 90-day strengths from this file.

Target plant for M01, M12, M13, M21: Loire Plant