hic trial glossary

Synthetic training content. Not a real Holcim trial report.

HIC trial glossary (synthetic)

> Training glossary for Gemini document search. Not a Holcim standard.

Clinker factor

The mass fraction of clinker in the binder. A clinker factor of 0.52 means 52 percent clinker. Lower is the usual HIC goal in this trial, provided the mix still meets spec.

LC3

Limestone calcined clay cement. In this training set, **LC3-50** targets about 50 percent clinker with calcined clay and limestone. **LC3-35** is a higher-clinker variant in the same family.

CEM I control

Ordinary Portland-style control mix in this trial. Clinker factor about 0.95. Used only as a laboratory benchmark. Not a plant recommendation by itself.

CEM II/A-LL

Portland-limestone style blend in this trial. Clinker factor typically about 0.70 to 0.75 in the synthetic set.

Spec strength

For HIC-LC3-24, the 28-day compressive-strength spec is **42.5 MPa** (CEM 42.5 class) on EN 196-1 mortar cubes. Other ages have no numeric spec in this glossary.

Pass versus spec

A row passes when ‘Compressive_Strength_MPa‘ is greater than or equal to

‘Spec_Strength_MPa‘ at that age. Only 28-day pass/fail is used for handover decisions.

Handover ready

‘Handover_Ready‘ is **Yes** only when all of the following are true for the mix:

1. ‘Trial_Stage‘ is Plant-ready
2. The mix?s **28-day** compressive strength is at or above 42.5 MPa
3. The water-demand note in the limitations file has been acknowledged (higher demand than CEM I)

If any item is false, ‘Handover_Ready‘ is **No**. Do not treat a 1-day or 7-day pass as handover ready.

Trial stages

- **Lab screening:** first cubes, not for plant
- **Scale-up:** extra batches, still HIC-owned
- **Plant-ready:** mix card may be issued if handover ready is Yes

Loire Plant

Synthetic target plant for this training story. Not a real site report.